

CONSTRUCTION NOTES:

- 1 INSTALL 4-EACH WORD MESSAGE SIGNS "TRAFFIC CONTROL CHANGE AHEAD", ON TYPICAL W8-1 (36"x 36") PLACARDS WITH 2 ORANGE FLAGS PER SIGN ON EACH APPROACH A MINIMUM OF 300- FEET FROM INTERSECTION STOP BARS AT TIME OF ACTIVATION OF SIGNAL.
- 2 CONTRACTOR TO REMOVE 4 EA. EXISTING STOP AND STREET NAME SIGNS AT INTERSECTION UPON ACTIVATION OF THE SIGNAL AND SHALL SALVAGE THESE SIGNS TO THE CITY PER SIGNING GENERAL NOTES, THIS SHEET.

SIGNING GENERAL NOTES:

- 1. ALL SIGNS SHALL BE IN COMPLIANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), THE ADOT SIGNING AND MARKING STANDARDS, THE TRAFFIC ENGINEERING MANUAL OF APPROVED SIGNS, THESE PLANS, AND THE SPECIAL PROVISIONS.
- 2. ALL FACES OF BOLTS USED FOR MOUNTING SIGNS SHALL BE PAINTED THE SAME COLOR AS THE SIGN PANEL.
- 3. ALL STATION LOCATIONS ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR STAKING ALL NEW LOCATIONS FOR SIGNS FOR THE ENGINEER'S REVIEW AND APPROVAL.
- 4. THE BOTTOM OF EACH SIGN SHALL BE AT LEAST 7 FEET ABOVE THE NEAREST EDGE OF PAVEMENT, TOP OF CURB OR SIDEWALK AND AT LEAST 7 FEET ABOVE THE GROUND UNDER THE SIGN UNLESS OTHERWISE NOTED.
- 5. THE HORIZONTAL OFFSET FOR THE SIGNS IS 6 FEET MIN. TO 8- FEET MAXIMUM FROM FACE OF CURB TO NEAR EDGE OF THE SIGN, UNLESS OTHERWISE NOTED ON THE PLANS. WHERE NO CURB EXISTS, THE DISTANCE IS 12 FEET FROM THE EDGE OF PAVEMENT TO THE NEAR EDGE OF THE SIGN. THE SOUTHBOUND SIGN POST TO BE LOCATED 4.5 FEET BEHIND THE FACE OF CURB TO KEEP SIGN WITHIN EXISTING RIGHT-OF-WAY.
- 6. EXISTING SIGNS NOT SHOWN ON THE PLANS DO NOT NEED TO BE REMOVED UNLESS SO NOTED. IF CONSTRUCTION ACTIVITIES REQUIRE THE REMOVAL OF SIGNS, NEW SIGNS SHALL BE INSTALLED AS NEAR AS POSSIBLE TO THE PREVIOUS LOCATION AS DIRECTED BY THE ENGINEER, UNLESS OTHERWISE SPECIFIED IN THE PLANS.
- 7. THE CONTRACTOR SHALL INVENTORY ALL SIGNS TO BE REMOVED OR COVERED, AND NOTE DAMAGED SIGNS TO THE ENGINEER AT THE TIME OF COVERING OR REMOVAL. ALL SIGNS DAMAGED BY COVERING OR REMOVAL DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AT NO COST TO THE CITY.
- 8. ALL SALVAGED SIGNS TO BE DELIVERED TO THE CITY PUBLIC WORKS MAINTENANCE YARD LOCATED AT 3700 E. ANDY DEVINE AVE. CONTACT BLAKE CHAPMAN AT (928)757-7467 FOR COORDINATION.
- 9. CONTRACTOR TO INSTALL U-CHANNEL SIGN POSTS & FOUNDATIONS PER ADOT 2002 SIGNING & MARKING STANDARD DRAWINGS & ADOT SPECIFICATIONS.
- 10. THE SIGNING PLANS MAY BE MODIFIED AS DIRECTED BY THE ENGINEER.




D			
C			
B			
A			
	REVISION DESCRIPTION	BY	DATE APP.

ASBUILT INFORMATION	
DATE OF ACCEPTANCE	
INSPECTED BY	
REVISED BY	
CHECKED BY	
ADEQ FILE NUMBER	
DATE OF ADEQ APPROVAL	
CITY CONTRACT NUMBER	
CONTRACTOR	

REFERENCE DRAWINGS	
03-ST-0033	
03-W-0022	
03-S-0023	
01-ST-0057	

CITY OF KINGMAN
ENGINEERING DIVISION
 310 NORTH 4TH STREET
 KINGMAN, ARIZONA 86401
 PHONE (928) 753-8122 FAX (928) 753-8118

DESIGNED BY	D. CASSON
DRAWN BY	D. CASSON
CHECKED BY	G. HENRY
DATE DRAWN	4-3-09
HORIZ. SCALE	N.T.S.
VERT. SCALE	N.T.S.



SIGNING & STRIPING PLAN
BANK STREET
AT GORDON DRIVE

SHEET	4
OF	4
DRAWING	ENG07-022